Diag. Cht. No. 4116-2.

FORM C&GS-504

U.S. DEPARTMENT OF COMMERCE Environmental science services administration coast and geodetic survey

DESCRIPTIVE REPORT

Type of Survey HYDROGRAPHIC

Field No. PF 10-6-66 Office No. H-8890

LOCALITY

State HAWAII

General locality KAHOOLAWE ISLAND

Locality CAPE KUIKUI NE SHORE

19...66

CHIEF OF PARTY

CDR G.L. SHORT

LIBRARY & ARCHIVES


DATE 1 8 NOV 1970

USCOMM-DC 87022-P66

DRM C&GS-537 U.S. DEPARTMENT OF COMMERCE COAST AND GEODETIC SURVEY	REGISTER NO.
HYDROGRAPHIC TITLE SHEET	
	н-8890
INSTRUCTIONS - The Hydrographic Sheet should be accompanied by this form, filled in as completely as possible, when the sheet is forwarded to the Office.	FIELD NO. PF 10-6-66
State HAWAII	
General locality KAHOOLAWE ISLAND	
Locality CAPE KUIKUI NE SHORE	
Scale 1:10,000 Date of surv	•
Instructions dated 12/6/65 Project No.	OPR 419
Vessel USC&GS Ship PATHFINDER	
Chief of party CDR G.L. SHORT	
Surveyed by G.L. SHORT, R. ALLBRITTON, E. GELB,	F. SMTTH. L. CASANOVA
Soundings taken by echo sounder, hand lead, pole	•
Graphic record scaled by SHIP'S PERSONNEL	
•	
Graphic record checked by SHIP'S PERSONNEL	
Protracted by SHIP'S PERSONNEL Automat	ted plot by
Soundings penciled by SHIP'S PERSONNEL	
Soundings in fathoms that at MKW MLLW	

XWW 2/14/94

USCOMM-DC 19086



Descriptive Report to accompany Hydrographic Survey H-8890 Field No. PF 10-6-66

USC&GSS PATHFINDER

CDR G. L. Short Cmdg.

1966

Scale 1:10,000

A. PROJECT

This survey is part of OPR 419 with original instructions dated October 25, 1960 to the Survey Ship Surveyor and has various amendments, supplements and revisions. Revised Instructions: Project OPR 419-Hawaiian Islands,

December 6, 1965 superseded all previous instructions and were the instructions by which the survey was conducted.

B. AREA SURVEYED

The area surveyed was the north east coast of Kahoolawe and was centered around the Cape Kuikui area. It was bounded on the west by longitude 156 37' and on the north by latitude 20 38' and on the east by a SE line starting at latitude 20 38' and longitude 156 33' and ending at \(\sqrt{156} \) 31' long. and 20 35.5' latitude. The shoreline is deserted and accessible by skiff or by foot overland. The island is a military reservation and not frequented by civilians. The coastline is rocky with occasional sandbeaches. Survey work started March 23, 1966 and ended April 11, 1966.

The survey junctions with contemporary surveys

H-8891

PF 10-4-66 on the west and PF 10-7-66 on the south.

On the north and east the survey junctions with H-8679 (1962)

and H-8583 which are 1:20,000 and 1:40,000 scales

respectfully. Prior survey of the area is Reg. #2728

conducted in 1904 and is of 1:20,000 scale.

C. SOUNDING VESSEL

All hydrography was accomplished by the Ship PATHFINDER and it's launches.

VESSEL	COLOR	DAY LETTER	
PATHFINDER	blue	upper case	
ML #2	violet	lower case	
ML #4	brown	lower case	V

D. SOUNDING EQUIPMENT

The Paytheon DE 723 fathometer were used in determining depths. The following units were used:

VESSEL	UNIT
PATHFINDER	#557
ML #2	#940
ML #4	# 1 41

The maximum depth obtained was 104 fathoms. Motor launches were used in depths of 0 fathoms to approximately 50 fathoms and the ship in areas of 20-100 fathoms.

Instrument corrections for the launches were determined by bar-checks at 1,2 and 4 fathoms, twice daily.

Velocity corrections were obtained from an analysis of oceanographic data obtained at stations taken in the

Hawaiian Islands in early 1966 by the Ship PATHFINDER.

For details see references in section Q.

E. SMOOTH SHEET

To be filled in by smooth plotter.

Soe Ensign's Lovell Genzlinger's Report attacked.

F. CONTROL

Advance manuscripts were used to plot the photogrametric control. They are T-12123 and T-12124 and were compiled in 1962. Two signals were located by sextant cuts.

They were NIP and VIA. The cuts are in Vol. 4 on pages 4,5,6,7,48,49 and 50. Three triangulation stations were used on the sheet as control. They are on the Old Hawaiian Datum.

Some trouble was experienced with control because signals NIP and VIA were originally phofo-hydro located and were in error. As a result the lines were eratic and were replotted after the correct location was determined.

G. SHORELINE

Shoreline was taken from T-12123 and T-12124. Shoreline was verified by a shoreline verification run conducted on April 9, 1966. Some additional areas were marked as foul. Some inshore rocks and shoal areas were obscured by the texture and coloring of the water.

These areas were located and sketched on April 9, 1966.

In general it is impossible to obtain least depth over submerged rocks or rocks awash or to determine the

low water line due to heavy surf conditions.

H. CROSSLINES

Crosslines constituted more than 7.3% of the linear miles run. There were no major discrepancies in crossings.

Crossings were within two fathoms without corrections

for tides or instruments. Some difficulty was encountered in the region of long. 156 34' 30" and lat. 20 36' 30"

but was resolved when signals NIP and VIA were relocated and the days (c day ML#2) work replotted.

I. JUNCTIONS

Junctions with PF 10-4-66 and PF 10-7-66 were sufficent and all soundings crossed with the exception of some Resolver by Smooth soundings in the region of long. 156 32' 15" and Philip see Ending 1 lat. 20 35' 15". The soundings between positions 59a, 60a and 61a for ML#3 on PF 10-7-66 were scanned incorrectly. The values at the crossing do check if the depths are corrected. They should be corrected in the volumes and on the boat sheet. Soundings and junctions with H-8679 (1961) and H-8583, are satisfactory both in agreement and overlap. The largest single discrepancy is four fathoms.

See smooth plotters J. COMPARISON WITH PRIOR SURVEYS

There are no pre-survey items to be investigated on this sheet. On prior survey Reg. #2728 there were soundings of 11 and 16 fathoms indicated in about 35 fathoms of water. A development was run but no indication was found of a shoal. It is of interest to note that these shoal aoundings were not on the chart; which indicates that

they were probably disproven earlier. Otherwise the soundings agreed within acceptable limits (plus or minus two fathoms).

K. COMPARISON WITH CHART

Chart #4130 published in August of 1964 is a 1:80,000 scale chart showing Kahoolawe Island. No new important dangers to navigation were discovered. Most soundings agreed as nearly as they could be transferred.

L. ADEQUACY OF SURVEY

This survey is adequate for charting and should supersede previous surveys.

M. AIDS TO NAVIGATION

There are no aids to navigation on this sheet.

N. STATISTICS

VESSEL	POSITIONS	LINIER MILES
PATHFINDER ML #2 ML #4 Total	251 +19 771 109 104 1131 1149	48.2 94.3 15.0 157.5 See Volume No 4 pages 18 Lo 51, mel.

There were approximately 10.0 square nautical miles of area covered by this hydrographic survey. There was one magnetic station observed at EGG 2, 1963. There were no bottom samples taken.

O. MISCELLANEOUS

None

P. RECOMMENDATIONS

None from boat sheet.

R. REFERENCES

A copy of a letter from the Director, Pacific Marine Center, dated 22 March 1966, onthe subject of bottom samples, is attached.

Fidel T. Smith Lt(jg) USESSA

USC&GSS PATHFINDER OPR. 419 PF 10-6-66

SMOOTH PLOTTER'S REPORT

The projection grid and triangulation stations were plotted by the electronic digital plotter at Pacific Marine Center.

Trouble was experienced in plotting signals NIP and VIA. The signals were originally located as photo-hydro signals, but were in error. Sextant cuts were then taken to relocate the signals. They were transferred directly from the manuscript to the smooth sheet, but it appeared the cuts had not been carefully plotted on the manuscript and were in error. They were replotted directly on the smooth sheet with a three-arm steel protractor using the sextant angles in the volume and no more trouble was experienced when the signals were used.

With all correctors applied, crosslines were in good agreement. The largest error in crossings in the area of 156°33'15" and 20°36'15" was 1.4 and 1.6 fms. The entry of correctors and the reduction of soundings were checked on the lines concerned, but exact agreement could not be made. Hydrography in the small bay between signals EGG and FUZ was difficult as a fix was impossible to obtain. Sounding lines close to shore were difficult to resolve as the area was quite rocky and signals were hard to see for a fix.

Phase corrections were entered using the average of the phase changes for each day on each vessel. To find the mean correction term for scale changes, the phase changes were grouped by day for each vessel. Similar phase changes, i.e., all A-B changes were grouped together and all B-C changes were grouped together. The mean was found of each group and yielded a mean corrector for each phase change of each day. Only good readable phase changes on a fathogram were used and the unclear phase changes were disregarded.

The phase correctors were figured accumulatively, i.e., if A-B mean corrector was +0.3 and B-C was +0.2, then the accumulative phase applied was +0.5 to all C scale soundings. It is, therefore, the addition of all mean phase correctors. down to that scale.

The mean corrector term corrects the deeper scale to agree with the next shoaler scale. The accumulative corrector term corrects the scale to the A scale.

Junctions could not be compared with sheets PF 10-4-66 and PF 10-7-66 because the smooth sheets were incomplete as of this date.

Under paragraph "I", the hydrographer mentioned that there was a discrepancy of 4 fathoms in comparing with prior surveys H-8679 and H-8583 in the area of Lat. 20 37 45 and Long. 156 35 50 (positions 117B to 125B). After all correctors, which amounted to an average of between plus 3 to 4 fathoms, were applied there was good agreement in

the junction soundings.

A development was plotted to investigate a shoal which was indicated in prior survey #2728. The development was not shown on the boat sheet but was on a separate overlay. No indication of a shoal was found from the development. No shoal soundings were indicated on the chart so probably it had been disproven earlier.

The survey is adequate for charting and should supersede previous surveys.

> Lowell Genzlinger Ensign USESSA

Louel Genglinger

APPROVAL SHEET

REGISTRY NO. 8890 (PF 10-6-66)

The field work on this sheet was inspected where conditions permitted. The records and smooth sheet have been examined and approved.

The survey is considered complete and adequate for charting purposes and no additional field work is recommended.

Date

G.L. Short

Cmdg. Ship PATHFINDER

TIDE NOTE

Aydrography was controlled by a bubbler tide gage installed at Kaumalapau harbor on Lanai Island. However aue to the poor records received (see attached memo dated 11 August, 1966) the hourly heights were obtained from Washington to reduce the soundings. The hydrography was run using the 135 time meridian while the gage was on the 150 time meridian so 1 hour was added for the hourly heights. MLLW, computed from level records, is 1.9 feet above staff zero.

TIDE NOTE FOR HYDROGRAPHIC SHEET

October 31, 1967

Nautical Chan Division:

Pacific Marine Center

Plane of reference approved in 8 volumes of sounding records for

HYDROGRAPHIC SHEET 8890

Locality: Kahoolawe Island, Hawaii

Chief of Party: G.L. Short (1966)

Plane of reference is mean lower low water

Tide Station Used (Form C&GS-681):

Honolulu, Hawaii

Height of Mean High Water above Plane of Reference is as follows: 1.4 feet

Remarks

G. M. Signious
Chief, Tides and Currents Branch

USCOMM-DC 6680-P64

Memorandum

ENVIRONMENTAL SCIENCE SERVICES ADMINISTRATION

The Commanding Officer USC&GS Ship PATHFINDER 1801 Fairview Avenue, East Seattle, Washington 98102

DATE: August 11, 1966

In reply refer to: C3312-155-CSS 8

FROM

Chief, Tides Section Oceanography Division

SUBJECT:

Tidal data, OPR-419

Requested hourly heights are enclosed. Honolulu tabulations are furnished in lieu of Kaumalapau observations. The Kaumalapau record showed evidence of a shifting datum and had to be discarded. MLLW, computed from level records, is 1.9 ft. above staff zero.

Mean lower low water at the other stations is:

Kamalo

2.2 ft. on staff No. 1

Kaunakakai

3.2 ft. on staff

Reference to new staff at Kamalo and requested July observations at Honolulu will be furnished as soon as possible.

Marka G. Wim

Martha A. Winn

Enclosures

GEOGRAPHIC NAMES PENCILLED ON SMOOTH SHEET H-8890 (PF-10-6-66)

ALALAKEIKI CHANNEL

CAPE KUIKUI

HAKIOAWA

KAHOOLAWE ISLAND

KANAPOU BAY

KEALAIKAHIKI CHANNEL

KUHEIA BAY

LAE O ULE

LAE O KUIKUI

TECSESS PATHFINETT G. L. Short, Condg. 1936

Volocity corrections to be applied to all 1986 hydrography on sheets

77 10-5-65, 77 10-1-66, 77 10-2-66, 77 10-3-66, 77 10-4-66, 77 20-2-66, 77 20-1-66, 77 20-2-66

CO MEFCK (Chs)	CORRECTION (fins)	io depen (ens)	CONSECTION
0.0 - 5.0	0.00	t 72.6 – 77.2	3.2
3.1 - 5.3	0.3	77.3 – 82.0	3.4
5.4 - 7.8	- 0.2	22.1 – 26.7	3.5
7.9 - 10.0	0.3	E5.8 - 91.3	3.8
10.1 - 12.3	2 0.4	91.4 - 95.8	4.c
12.4 - 14.5	0.5	95.9 – 100.5	4.2
14.6 - 16.8	0.6	100.6 - 112	4.5
14.9 - 19.5	0.7	113 - 125	5. 0
19.6 - 21.5	0.8	126 - 140	5.5
21.6 - 3.8	0.9	141 – 158	6.0
23.9 - 26.0	1.0	159 - 178	6.5
25.1 - 28.3	2,1	179 - 200	7.0
28.4 - 31.6	1.2	201 - 232	7.5
31.7 - 35.2	2,4	233 - 273	8.0
36.3 - 41.0	1.6	274 - 320	8.5
41.1 - 45.3		321 - 368	9.0
45.4 - 50.0	2.0	369 - 418 .	.9.5
50.1 - 54.5	2.2	419 - 460	20.0
54.6 - 59.0	2.4	461 - 495	
59.1 - 63.5	2,6	495 - 527	0
63.6 - 88.0	2.8	528 - 558	1.5
68.1 - ?2.5	3.0	559 - 584	12.0

[&]quot;All volceity corrections are confitive and to be added

SHIP PATHFINDER OPR 419

,	DRAFT
- 4	CORRECTIONS

<i>.</i>	DATE,	DRAFT(ft) mdshps	DRAFT(fms) mdshps	INITIAL	FATH. INSTR.	DRAFT CORR.
2	Feb. 27	15.0	2.5	2.0	-0.1	0.4
	Mar. 12 13567 2156 27 28 29 30	14.7 14.5 14.3 13.9 15.0 14.9 14.8 14.7 14.8 14.2		2.0 2.0 2.0 2.0 2.0 2.0 2.0 2.0 2.0 2.0	-0.1 -0.1 -0.1 -0.1 -0.1 -0.1 -0.1 -0.1	33330000000000000000000000000000000000
		15.0 15.0 14.0 14.0 14.0 14.0 14.0 14.0 14.0 14	55555444444444533333333333333333333333	2.0 2.0 2.0 2.0 2.0 2.0 2.0 2.0 2.0 2.0	-0.1 -0.1 -0.1 -0.1 -0.1 -0.1 -0.1 -0.1	中心

HAWAIIAN ISLANDS OPR-19 USC&GS Ship PATHFINDER CDR G. L. Short, Cmdg. 1966 ECHO CORRECTIONS PF 10-6-66

vessel	date	day	corrector 0-31 fms. 31-101fms	٠.
ML #2	3/23/66	a	+0.4 +0.4	
11	3/25/66	b	+0.3 +0.2	
13	3/28/66	c	+0.3 +0.2	
tř	3/29/66	đ	+0.3 +0.2	
11	3/30/66	e	+0.4 *0.4	
11	4/9/66	f	+0.4 +0.4	
19	4/11/66	g	+0.4 +0.4	
ML #4	3/24/66	a	+0.4 +0.4	

USC&GSS PATHFINDER
G. L. Short Cmdg.
Opr. 419
PF 10-6-66
Phase Corrections

Vessel	Day	Scale	Correction
PATHFINDER	A	A - B B - C	+0.7 +1.5
	В	A-B B-C	+0 _• 5
	С	A-B B-C	+0.5 +1.0
Launch #2	æ b c d e f	A-B No scale A-B A-B A-B A-B A-B A-B	+0.2 changes 0.0 -0.1 0.0 0.0 -0.1
Launch #4	æ	No good s	cale changes

SIGNAL LIST

NAME	SOURCE	$\underline{\mathtt{TYPE}}$
OPU MOLO WET	EGG 2,1963 MOLOKINI 2,1950 WET 2,1963	TRIANGULATION
ACE ART BED BUM CAT DOC DUN EGG FUZ GEM HOP ION JIB KEN LAD MAX OAK PRO RIO SKI TOM WAG YEA ZOO	T-12124 T-12123 T-12124 T-12123 T-12123 T-12124 T-12124 T-12123 T-12124	PHOTO-HYDRO
NIP VIA	Vol. 4 pp 4,5,6, 7,48,49and 50	HYDROGRAPHIC

Memorandum

TO

: Director

Pacific Marine Center

DATE: March 15, 1966

FROM : Commanding Officer

Ship PATHFINDER

SUBJECT: REVISED INSTRUCTIONS, PROJECT OPR-419 DATED DECEMBER 6, 1965

Obtaining bottom characteristics around Kahoolawe Island is not considered safe due to the presence of unexploded ordnance in the restricted area around the island. If the bottom sampler dropped on a piece of ordnance equipped with an impact fuse, or any other piece with an unstable explosive, an explosion damaging to the ship and personnel could result. The ship is not anchored at Kahoolawe Island because of this danger.

Bottom characteristics from previous surveys are shown on the current charts of the area.

It is requested that the subject instructions be amended to omit bottom sampling in the restricted area surrounding Kahoolawe Island.

....TASE.L....

...EDatHOat....

.....M∆∆.....

....Supp.....

....Whso.....

....ರ೨೦೬೦.... ...Phys...

... (Gi (G)...

بالمنالية

_.inst..

B320.

Returner.

ARTMENT OF COMMERCE COAST AND GEODETIC SURVEY

DATE: 22 March 1966

In reply refer to:4050/01.3-5 **CF22**

UNITED STATES GOVE MENT

Memorandum

: Commanding Officer USC&GSS PATHFINDER

BROM : Director **PACMARCEN**

SUBJECT: Bottom Samples - Kahoolawe Island

Permission is granted to omit bottom samples in the vicinity of Kahoolawe Island, At no time are project instructions intended to jeopardize the safety of personnel or equipment.

A statement in the pertinent descriptive reports stating why bottom samples were omitted is all that is required. A formal amendment to the project instructions will not be written.



FORM 197 (3-16-55)

GEOGRAPHIC NAMES Survey No.H-8890	/-	Char.	Ac. Or	S Wada	of act and	Or och Mad	Cuide	ASO WENSIL	N. S. J. S.	
Name on Survey	A	B	C		E	or F	ς. G_	Н	S. K	
Alalakeiki cho	nne	/								1
Cape Kuikui							ļ	ļ		2
Hakioawa (P Kahoolawe Is	oint)								3
Kahoolawe Is	Izni	1	<u> </u>							4
Kanapou Bay Kealaikahiki	,	<u>.</u>				 				5
Kealaikahiki	Cha	nne	/						 	. 6
Kuheia Bay										7
Puhi Koheo	10/10	7				}				8
Ule Point			<u> </u>							9
	, .									10
										11
										13
								 		14
									/	15
		·		11.00				-		16
										17
										18
						ļ				19
										20
					to the total	RED I	RY			21
					PART	121	1	3/) }	22
,					CART	OGRAP	HIC T	CHNIC	IAN	23
								1178 8		24
					APP	ROVEL	BX		2011	25
	·			C)	10	g	VI A	W	en v	26
				· · · · ·	GHI	ef Gis		ri Mil		27

FORM C&GS-946 (REV. 11-65) (PRESC. BY HYDROGRAPHIC MANUAL 20-2, 6-94, 7-13)

U.S. DEPARTMENT OF COMMERCE ENVIRONMENTAL SCIENCE SERVICES ADMINISTRATION COAST AND GEODETIC SURVEY NAUTICAL CHART DIVISION

HYDROGRAPHIC SURVEY STATISTICS HYDROGRAPHIC SURVEY NO. <u>H-8890</u>

RECORDS ACCOMPANYING SURVEY: To be completed when survey is registered.

RECOR	RD DESCRIPTION		АМО	AMOUNT		RECORD DESCRIPTION			
SMOOTH SHEET			1		BOAT SHEETS		BOAT SHEETS		2
DESCRIPTIVE RE	EPORT		1		OVERLAYS			1	
DESCRIPTION	DEPTH RECORDS	HORIZ. RECO		PRINT	routs	TAPE ROLLS	PUNCHED CARDS	ABSTRACTS/ SOURCE DOCUMENTS	
ENVELOPES									
CAHIERS	1								
VOLUMES	8								
BOXES									
TARMEET DRINTS	(Tist)								

1-SHEET PRINTS (LIST)

I-12/23 and T-12/24

SPECIAL REPORTS (List)

OFFICE PROCESSING ACTIVITIES The following statistics will be submitted with the cartographer's report on the survey

	AMOUNTS					
PROCESSING ACTIVITY	PRE- VERIFICATION	VERIFICATION	REV	IEW	TQTALS	
POSITIONS ON SHEET					1149	
POSITIONS CHECKED		520			_	
POSITIONS REVISED		38				
DEPTH SOUNDINGS REVISED OF added		325			1	
DEPTH SOUNDINGS ERRONEOUSLY SPACED		197				
SIGNALS ERRONEOUSLY PLOTTED OR TRANSFERRED						
	TIME (MANHOURS)					
TOPOGRAPHIC DETAILS		16				
JUNCTIONS		40				
VERIFICATION OF SOUNDINGS FROM GRAPHIC RECORDS		144				
SPECIAL ADJUSTMENTS						
ALL OTHER WORK		200				
TOTALS		400				
PRE-VERIFICATION BY		BEGINNING DATE		ENDING	DATE	
VERIFICATION BY Lehm	aw	BEGINNING DATE Sept 22 1969 BEGINNING DATE		Dec 2, 1969		
REVIEW BY		BEGINNING DATE		ENDING	DATE	

U.S. DEPARTMENT OF COMMERCE ESSA COAST AND GEODETIC SURVEY

VERIFIER'S REPORT HYDROGRAPHIC SURVEY, H_-\(\frac{7890}{2}\)

INSTRUCTIONS - This form serves to identify items of a check list in verification together with items which are separately reported to the Reviewer. The form is not to be forwarded to the Reviewer. A report, which is prepared for the Reviewer, should identify items by number and letter and will be filed in the Descriptive Report until the survey is reviewed.

- CL Check List Items: should be checked as having been completed during the verification processes.
- R Report Item: This column refers to those items reported to the reviewer and is used to indicate the items discussed.

						1
Part I - DESCRIPTIVE REPORT	CL	R	Part III - JUNCTIONS (Continued) 10. Junctions with contemporary surveys were	CL	R	
Note: The verifier should first read the Descriptive Report for general information and problems.			satisfactory except as follows:			
 The Descriptive Report was consulted, paragraphs checked if found satisfactory, and notations were made in soft black pencil regarding action taken. Remarks Required: None 	V		Remarks Required: Consider conditions after adjustments have been made; note adjustments made. Make special notes of Butt junctions and areas which are SUPERSEDED.			
2. Soundings originating with the survey and mentioned in the Descriptive Report have been verified and checked in soft black pencil, including latitude and longitude, together with position identification. Remarks Required:None	/		Part IV - VOLUMES 11. All items affecting the plotting of the survey which are entered in the remarks columns of the sounding records were noted and check marked. In all cases appropriate action was taken and exceptions noted in the volumes.	V		
3. All reference to survey sheets mentioned in the Descriptive Report should include registry number and year. added in ponch.	/		Remarks Required: None 12. Condition of sounding records was satisfactory		·	$\frac{1}{1}$
Remarks Required: None Descriptive Report.			except as follows:			
ort II - SHORELINE AND SIGNALS . Source of shoreline signals Advance Manuscr, Remarks Required: List all surveys	. /		Remarks Required: Mention deficiencies in completeness of notes or actions for the following:			
a. Give earliest and latest dates of photographs we dot			 (a) rocks √ (b) line turns √ (c) position values of beginning and ending of 			
b. Field inspection date c. Field Edit date July 1965 d. Reviewed-Unreviewed (for Hydro)			lines (d) bar check or velocity correctors			
5. The transfer of contemporary topographic information was carefully examined and reconciled with the hydrography.	1		(e) time recording (f) notes or markings on fathograms (g) was reduction of soundings accurately done?			
Remarks Required: Discuss remaining differences.	_	<u> </u>	(h) was scanning accurate?			١
6. The plotting of all triangulation stations, topographic stations and hydrographic signals has been checked and noted in processing stamp No. 42 on the smooth sheet.	V		(i) were peaks at uneven intervals missed?			
Remarks Required: None		<u> </u>	(k) references to adjacent features	-		ᅱ
7. Objects on which signals are located and which fall outside of the high-water line have been described on the sheet. Remarks Required: List those signals still unidentified.	V.	-	Part V - PROTRACTING 13. All positions verified instrumentally were check marked in color in the sounding records, and verifier initialed the processing stamp. Remarks Required: None			
Part III - JUNCTIONS Note: Make a cursory comparison preliminary to inking soundings in area of overlap.			14. The protracting and plotting of all unsatisfactory crossings were verified.	/		
8. All junctions of contemporary or overlapping sheets were transferred in colored ink and overlapping curves were made identical.	V		Remarks Required: None		-	
Remarks Required: None The notation in slanted lettering "JOINS H (19)" was added in colored ink for all veri- fied contemporary adjoining or overlapping sheets. Those not verified are shown in penci	1.7		15. All detached positions locating critical sound ings, rocks, buoys, breakers, obstructions, kelp, etc., were verified and the position numbers are legible.	1		
Remarks Required: None			Remarks Required: None			(2 × 4

Part V - PROTRACTING (Continued) Patt VIII - AIDS TO NAVIGATION CL CL R 16. The protracting was satisfactory except as 26. All fixed aids located together with those on follows: the contemporary topographic sheets, have Remarks Required: -- Refers to protracting been shown on the survey. in general except for specific faults repeated often, or faults in control information, which Remarks Required: -- Conflicts of any nature required considerable replotting or adjustments listed. 17. The protractor has been checked within the 27. All floating aids listed in the Descriptive Report should be verified and checked last three months. in soft black pencil, including latitude Remarks Required: -- Date of check, type of and longitude and position identification. transparent Long & Short Oct. 17, 1969 Remarks Required: -- None Part VI - SOUNDINGS 18. All soundings are clear and legible, and criti-Part IX - BOAT SHEET cal soundings are a little larger than adjacent soun dings 28. The boat sheet was constantly compared with the smooth sheet with reference to Remarks Required: -- None notes, position of sounding lines and supplemental information. 19. Sounding line crossings were satisfactory Remarks Required: -- None except as follows: 29. Heights of rocks awash were correctly re-Remarks Required: -- Discuss adjustments. duced and compared with topographic information. 20. The spacing of soundings as recorded in the records was closely followed; Remarks Required: -- Note excessive conflicts with topographic information. Remarks Required: -- None Part X - GENERAL 30. All information on the sheet is shown in 21. The scanning, reduction, spacing, plotting of questionable soundings have been verified. accordance with figures 82 and 83 in the Hydrographic Manual (Pub. 20-2). Remarks Required: -- None Remarks Required: -- None 22. The smooth plotting of soundings was satisfactory except as follows: Remarks Required: - Refer to legibility, errors in spacing, and errors in numbers - but 31. Unnecessary pencil notes have been removed from the sheet. not to errors in scanning.

good lagibility - Some arrord in

Spacing - and scanning. Remarks Required: -- None Part VII - CURVES 32 Degree, minute values and symbols have 23. The depth curves have been inspected before inking.

Remarks Required: -- By whom was the penciled curves inspected. 4 7/18 Verifier. been checked; also electronic distance arcs have been properly identified and checked on the smooth sheet. 24. The low-water line and delineation of shoal Remarks Required: - None areas have been properly shown in accordance with the following: a. From T-Sheet in dotted black lines V 33. The bottom characteristics are adequately b. From soundings in orange ... shown. c. Approximate position of sketched curve isy Remarks Required: -- None dashed orange d. Approximate position of shoal area not v sounded in black dashed Part XI - NOTES TO THE REVIEWER 34. Unresolved discrepancies and questionable Remarks Required: -- None soundings. 25. Depth curves were satisfactory except as follows: unshow offer. Jough. 35. Notation of discrepancies with photogrammetric survey inserted in report of unreviewed (This statement should not refer to the photogrammetric survey or on copy. manner in which the curves were drawn). Remarks Required: -- Indicate areas where curves could not be drawn completely because of lack of soundings. For some inshore areas 36. Supplemental information. a general statement is sufficient. Dec. 2,1969 Verified by Clarence R. Lehman

FORM C&GS-946A (11-65)

USCOMM-DC 36272-P65

H-8890 PF-10-6-66

D. SOUNDING EQUIPMENT

Stylus arm lengths were scaled for all fathograms; only on 3 days were appreciable corrections noted, they are:

"f" day Launch No. 2 echo sounder No. 940 - 0.5%

"g" day Launch No. 2 echo sounder No. 940 - 0.5%

"a" day Launch No. 4 echo sounder No. 141 - 1.5%. The percent of stylus arm correction was entered in the sounding volumes at the beginning of each day's work. The entries are made in red ink and correctors shown in the initial columns.

E. SMOOTH SHEET

Crossline descrepancy at Latitude 20°36'15" and Long-itude 156°37'15" as mentioned in the Smooth Plotter's Report was resolved by the verifier. The difficulty here was mostly erroneous reading of the fathogram in an area of pronounced spiking. See fathogram for "e" day Launch #2 of March 30, 1966.

G. SHORELINE

Smooth sheet shorelines have been checked by the verifier and compared to manuscripts T-12123 and T-12124 as well as the boat sheet shorelines. Verifier made only

minor corrections - mostly small ommissions such as elevation of rocks.

Η. CROSSLINES

About 8% of the sounding lines are cross lines.

The discrepancy mentioned in the ship's report has been resolved. The problem was mainly in the location of signal NIP which was corrected by the smooth plotter. addition of stylus arm corrector by the verifier further dismissed differences at the crosslines. All crossline soundings now appear to be satisfactory.

I. JUNCTIONS

Junction soundings from four different contemporary surveys have been transferred to this survey. They are:

H-8888 (1966) to the West shown in purple

H-8583 (1961) to the North shown in orange

H-8679 (1962) to the East shown in brown

H-8891 (1966) to the Southeast shown in red.

All junctions are complete and acceptable; depth curves have been flared in to join.

Respectfully submitted,

Clarence R. Lehman Carto. Tech.

Approval Sheet

This smooth sheet has been inspected and meets the requirements of the Hydrographic Manual. (Note: Exceptions are noted in the verifier's report.)


Examined and Approved


Cornelius A. J. Pauw Cartographic Tech.

William M. Martin Supervisory Carto. Tech.


Approved and Forwarded

K. William Jeffers, CDR, NOAA Chief, Processing Division, PMC





0,00 50



RECORD OF APPLICATION TO CHARTS

FILE WITH DESCRIPTIVE REPORT OF SURVEY NO.

H-8890

INSTRUCTIONS

A basic hydrographic or topographic survey supersedes all information of like nature on the uncorrected chart.

1. Letter all information.

2. In "Remarks" column cross out words that do not apply.

3. Give reasons for deviations, if any, from recommendations made under "Comparison with Charts" in the Review.

CHART	DATE	CARTOGRAPHER	REMARKS
4130	1-12-71	E: Frey	Fall Part Before After Verification Review Inspection Signed Via
	·		Drawing No. Examined for critical corrections
			Before
4116	4-15-71	Ja Trohan	Fall Part Before After Verification Review Inspection Signed Via
	/		Drawing No. 16 app'd mise conections the
			cht. 4130 dug. #14x
4179	5/10/71	J. Ho Hillan	Cht. 4130 dug. #14X Part After Verification Review Inspection Signed Via
	-		Drawing No. 9 Rocrifical Core at this scale at
		. 1/	time thru 4116 #16
4102	1/27/2	William	Full Part Before After Verification Review Inspection Signed Via
1100	1991		Drawing No. 28 app'd for cutical con one
B. P. J M. B	0		three cht 4116 dug +16
4180	3/15/12	E. Frey	Full Part Before After Verification Review Inspection Signed Via
1	3,19,12		Drawing No. 11 Appid for critical corrections only
			thru cht 4102 dwg #28
4115	7/20/73	C.S. Forbes	Part Part After Verification Review Inspection Signed Via
	1-1-		Drawing No. April For critical corrections thru whart
			4116 \$ 16.
1102	10/27/22	C.S. Forbes	Full Part Before After Verification Review Inspection Signed Via
7.0	721/1	C. J. J Ol Dej	
		•	Drawing No. Consider application final, No additional
A179	12/01/22	O.S. Forbes	Full Part Before After Verification Review Inspection Signed Via
HIII	12/01/11	C, Jo FORDES	The state of the s
			Drawing No. Consider application as Final No additiony
4120	10 2 77	00 5	Full Part Before After Verification Review Inspection Signal Via
4130	12-30-11	m. Sager	
			Drawing No. Examined Verified Survey - No correction
4.4.		0 =	Full Ran Before After Verification Range Language Signal Via
4116	12-30-11	M. Sager	
		CAT-I	Drawing No. Examamined thru chart 4130-
			No corrections, Consider Final application.
19320	5/7/92	J. Shorman	No Cors Fully appld.
······································			
	1		